

TABELA
robót ziemnych

Lokali- zacja	Powie- rzchnia		Średnia powierz- chnia		L	Objętość		Zużycie na miejscu	Nadmiar objętości		Suma algebraiczna	
	W	N	W	N		W	N		W	N	Odkład	Dokop
	m ²	m ²	m ²	m ²		m ³	m ³		m ³	m ³	m ³	m ³
2+300.00	0.14	0.27										
2+340.00	0.77	0.8	0.46	0.54	40.0	18.40	21.60	18.40	0.00	3.20		3.20
2+370.00	0.64	0.1	0.71	0.45	30.0	21.30	13.50	13.50	7.80	0.00	4.60	
2+400.00	0.45	0.15	0.55	0.13	30.0	16.50	3.90	3.90	12.60	0.00	17.20	
2+430.00	0.6	0.12	0.53	0.14	30.0	15.90	4.20	4.20	11.70	0.00	28.90	
2+460.00	0.59	0.1	0.60	0.11	30.0	18.00	3.30	3.30	14.70	0.00	43.60	
2+490.00	0.63	0.11	0.61	0.11	30.0	18.30	3.30	3.30	15.00	0.00	58.60	
2+520.00	0.45	0.26	0.54	0.19	30.0	16.20	5.70	5.70	10.50	0.00	69.10	
2+550.00	0.07	0.65	0.26	0.46	30.0	7.80	13.80	7.80	0.00	6.00	63.10	
2+580.00	0.01	1.09	0.04	0.87	30.0	1.20	26.10	1.20	0.00	24.90	38.20	
2+610.00	0.01	0.7	0.01	0.90	30.0	0.30	27.00	0.30	0.00	26.70	11.50	
2+640.00	0.69	0.03	0.35	0.37	30.0	10.50	11.10	10.50	0.00	0.60	10.90	
2+670.00	0.25	0.33	0.47	0.18	30.0	14.10	5.40	5.40	8.70	0.00	19.60	
2+700.00	0.31	0.31	0.28	0.32	30.0	8.40	9.60	8.40	0.00	1.20	18.40	
2+730.00	0.07	0.53	0.19	0.42	30.0	5.70	12.60	5.70	0.00	6.90	11.50	
2+760.00	0.04	0.59	0.06	0.56	30.0	1.80	16.80	1.80	0.00	15.00		3.50
2+800.00	0.11	0.45	0.08	0.52	40.0	3.20	20.80	3.20	0.00	17.60		21.10
						177.60	198.70	96.60	81.00	102.10		21.10